


BURBANK WATER AND POWER ADVANCED METERING INFRASTRUCTURE UPGRADE

JARED LEE, PE

CIVIL ENGINEER



**WATER AND
POWER**





CITY OF BURBANK

- 17.4 square miles
- Population of 105,000
- 17,000 AFY of potable water demand
- 3,300 AFY of recycled water demand
- No water rights - all our water must be imported/purchased

WATER METERING

- Advanced Metering Infrastructure (AMI) meter reads are obtained automatically
- BWP was among the first utilities to pilot and implement AMI in early 2010
- Although initially successful, BWP's AMI began to degrade at a rate exceeding industry standards
 - More than 25% of 27,000 AMI capable meters are not working
 - Hundreds more fail every month
 - System will fail in the next couple of years
 - Replacements are not available





PROJECT DESCRIPTION

- BWP needs to replace its water AML system
 - Wireless Wide Area Network and over 27,000 transmitters
- Retrofit or replace lids for wireless connectivity
- Keep existing meters and registers
- Interface with BWP's existing Customer Information Systems



PROJECT BENEFITS

- Reduce water usage by over 512 acre-feet per year
- Save almost 1.7 million kWh annually in electricity
 - Enough to power 256 single family homes per year
- Reduce CO2 emissions by over 380 metric tons from not having to import State Water Project Water
- Access to near real time data that can notify of abnormal water usage
- Reduce water loss/non-revenue water
- Improve water conservation/water accountability
- Comply with upcoming indoor water budget regulations

CEQA & PERMIT STATUS

CLASS 1
CATEGORICALLY
EXEMPT, NO OTHER
PERMITS REQUIRED

PROJECT BUDGET

Budget Category	Grant Request	Cost Share	Other Cost	Totals
A. Project Administration	-	-	-	-
B. Land Purchase/Easement	-	-	-	N/A
C. Planning/Design/Engineering/Environmental Documentation	-	-	-	COMPLETED
D. Construction/Implementation	\$1,000,000	\$7,000,000		\$8,000,000
Totals	\$1,000,000	\$7,000,000		\$8,000,000
Minimum Grant Amount Needed	\$250,000			

PROJECT SCHEDULE

Budget Categories	Start Date	End Date
A. Project Administration	January 2022	December 2024
B. Land Purchase/Easement	n/a	n/a
C. Planning/Design/Engineering/Environmental Documentation	January 2022	December 2022
D. Construction/Implementation	January 2023	December 2024

EXPECTED CHALLENGES/DELAYS



Supply Chain Disruptions and Lead Times



Water Meter Lid Retrofits



Integration with legacy systems and equipment

PRIORITIES AND CONSIDERATIONS UNDER WATER CODE §79707(B AND E) AND §79742(A AND F)

Leverage Funds

- Local funding from Approved FY 22/23 Budget

Employ New or Innovative Ideas

- Near instant Two-way communication between utilities and customers
- Track indoor & outdoor water usage
- Timely notification of leaks and abnormal usage

Greater Watershed Coverage

- Project affects BWP's entire service area - 17.4 square miles in the Upper LA River Watershed

Multiple Benefits

- Customers more attuned with water usage
- Saves 512 acre-feet/year of water
- ~1.7 million kWh of energy savings/year
- Greenhouse Gas reduction of over 380 metric tons CO₂/year

QUESTIONS?



JARED LEE, PE
CIVIL ENGINEER



JLEE@BURBANKCA.GOV



818-238-3528


Los Angeles County Public Works

La Crescenta Green
Improvement Project


Rafael Piamonte

Associate Civil Engineer

Project Location




Project Description




* Estimated Project Completion Date: February 2026

Project Description



Project Description



Project Description

- * Stormwater quality improvements
 - * 30 drywells
 - * 15,000 square feet of bioswales
 - * 19,000 square feet of permeable pavement
 - * 7.57 ac-ft per storm event
 - * 85th percentile capture, 150+ acre drainage area
- * Traffic safety improvements
 - * 4.1 miles of roadway rehabilitation
 - * Sidewalk and driveway repair and reconstruction
 - * Install Class II and III bikeways
 - * Construct ADA Compliant curb ramps/bulb-outs
 - * Stripe continental crosswalks
- * 47 new street trees

Project Benefits

Water Quality Benefits

Background condition

- Project area drains to Arroyo Seco Reach 2
- Arroyo Seco Reach 2 is subject to a bacteria TMDL
- Los Angeles River is subject to metals, nutrients, and bacteria TMDLs

Benefits

- Remove more than 60% of total metals
- Remove 64% of bacteria and nutrients

Methods used to quantify benefits

- Hourly 10-year WMMS simulation integrated in the SCWP Module
- Post-construction water quality monitoring

Project Benefits

Water Supply Benefits

Background condition

- Southern California has relied on imported water
- California has undergone lengthy droughts, which further impact local and regional water supply availability and needs

Benefits

- Increase water supply to Verdugo Groundwater Basin
- Provide 40 acre-ft of recharge each year

Methods used to quantify benefits

- Calculation of estimated dry and wet weather runoff volume captured (hourly 20-year WMMS simulation integrated in the SCWP Module)
- Install flow meter to quantify recharge volume

Project Benefits

Flood Control Benefits

Background condition

- Project is in an area with high population density and imperviousness

Benefits

- Provide new drainage infrastructure
- Divert urban runoff and increase downstream storm drain capacity

Methods used to quantify benefits

- Calculation of increased storm drain capacity
- Visual observation of reduced downstream flooding

Project Benefits

Open Space Benefits

Background condition

- Project area is highly impervious and lacking native vegetation

Benefits

- Plant 47 new trees
- Construct 15,000 sq-ft of bioswales with native drought tolerant landscaping
- Construct approximately 19,000 sq-ft of permeable paving
- Promote walking and biking and provide safe routes to La Crescenta Elementary School

Methods used to quantify benefits

- Measure the area of open space created

Project Benefits

GLAC IRWM Plan Missions

Improve
Water
Supplies

Enhance
Water Supply
Reliability

Improve
Surface Water
Quality

Preserve
Flood
Protection

Conserve
Habitat

Expand
Recreational
Access

Project Benefits

Statewide Priorities

Utilize Natural Infrastructure

- Install bioswales and permeable pavement
- Native and/or drought tolerant landscaping

Encourage Regional Approaches Among Water Users Sharing Watersheds

- Los Angeles County partners with City of Glendale to implement the proposed project

Drought Preparedness

- Provide groundwater recharge to Verdugo Groundwater Basin

Climate Resilience

- Plant 47 trees to sequester carbon
- Promote walking and biking to reduce green house gas (GHG) emission

Strengthen Partnership with Stakeholders

- Continuous coordination with Crescenta Valley Town Council and TreePeople
- A community outreach meeting was held May 2021

CEQA & Permit Status

CEQA/Permit Document (List all per EIF)	Start Date	End Date
Addendum to Program Environmental Impact Report	Ongoing	12/31/2023

* No applicable environmental/design-related permits

Project Budget

Budget Category	Grant Request	Cost Share	Other Cost	Totals
A. Project Administration	N/A	N/A	\$250,000	\$250,000
B. Land Purchase/ Easement	N/A	N/A	N/A	N/A
C. Planning/Design Engineering/ Environmental Documentation	N/A	N/A	\$1,250,000	\$1,250,000
D. Construction/ Implementation	\$2,000,000	\$2,000,000	\$3,700,000	\$7,700,000
Totals	\$2,000,000	\$2,000,000	\$5,200,000	\$9,200,000

Funding to be secured through County General Funds and SCWP Municipal Funds to supplement as needed.

Project Schedule

Budget Categories	Start Date	End Date
A. Project Administration	Ongoing	2/28/2026
B. Land Purchase/Easement	N/A	N/A
C. Planning/Design/Engineering/Environmental Documentation	Ongoing	10/31/2024
D. Construction/Implementation	2/1/2025	2/28/2026

Expected Challenges/Delays

- * Potential challenges and/or delays:
 - * O&M challenges related to training County staff/team
 - * Conversations are happening early on in preparation
 - * Finding funding
 - * County is applying for funding and will use available resources to make up difference
 - * Traffic-related construction impacts
 - * Working with the community early on to spread the word

Questions

Contact Person:

Rafael Piamonte

rpiamonte@dpw.lacounty.gov



Whitsett Fields Park North Stormwater Capture Project


IRWM ULAR Steering Committee

August 23, 2022

Noel Le

Civil Engineering Associate

Project Location



Communities:

- North Hollywood
- South Valley
- Valley Glen

Project Description

The Project is a multi-benefit project that will divert stormwater and urban runoff from a 78” storm drain into an underground infiltration gallery to infiltrate and replenish the San Fernando Groundwater Basin.


Drainage Area: 303 acres

Approx. Yield: 185 AFY

- * 740 single-family households annually


Partners:

- * LA Dept. of Public Works
- * LA Dept. of Recreation and Parks (RAP)




Project Benefits

GLAC Critical Needs	Response
Increase Water Supply	Project is estimated to infiltrate 185 AFY into the San Fernando Groundwater Basin (Basin).
Improve Surface Water Quality	Project will assist the City in meeting the Clean Water Act, Total Maximum Daily Loads (TMDLs) and comply with the Municipal Separate Storm Sewer System Permit (MS4) by removing pollutants such as trash, bacteria, metals, sediments, and nutrients.



Project Benefits


GLAC Critical Needs	Response
Address Climate Change	Infiltration into the Basin will increase local water supply, reducing the region's dependence on imported water supply. The Project will also plant 16 trees.
Reduce Flood Risk	Project will provide peak flow attenuation to the LA River and increase storm drain capacity, improving the efficiency of the flood control system.



Project Benefits

GLAC Critical Needs	Response
Enhance Open Space/Habitat/ Recreation	Project will enhance existing baseball fields with new shaded bleachers, dugouts, batting cages, sports lighting, and hydration stations.

These benefits would provide direct benefits to the DAC, especially the enhanced park amenities, additional trees, and improved flood control system.



Project Benefits

- * Statewide Priorities
 - * Utilize natural infrastructure
 - * Enables natural percolation to mimic predeveloped conditions
 - * Drought Preparedness
 - * Addresses long-term drought preparedness by contributing to sustainable water supply and reliability during water shortages
 - * Climate Resilience
 - * Reuses water more efficiently
 - * Reduces greenhouse gas emissions
 - * Will plant 16 new trees to provide carbon sequestration
- * Strengthens Partnerships with Stakeholders

CEQA & Permit Status

CEQA/Permit Document (List all per EIF)	Start Date	End Date
Initial Study/Mitigated Negative Declaration	Sep 2019	Sep 2021
Construction Stormwater General Permit	Dec 2024	Feb 2025
Encroachment Permit	Jan 2025	Mar 2025
Flood Control Permit	Aug 2021	Mar 2025

Project Budget

Budget Category	Grant Request	Cost Share	Other Cost	Totals
A. Project Administration	\$0	\$0	\$0	\$0
B. Land Purchase/ Easement	\$0	\$0	\$0	\$0
C. Planning/Design Engineering/ Environmental Documentation	N/A	N/A	\$1,168,300	\$1,168,300
D. Construction/ Implementation	\$3,430,000	\$14,564,293	\$0	\$17,994,293
Totals	\$3,430,000	\$14,564,293	\$1,168,300	\$19,162,593

Project Schedule

Budget Categories	Start Date	End Date
A. Project Administration	January 2018	August 2027
B. Land Purchase/Easement	N/A	N/A
C. Planning/Design/Engineering/Environmental Documentation	January 2018	September 2022
D. Construction/Implementation	March 2025	February 2027

Expected Challenges/Delays

	Challenges	Solutions/Mitigation Efforts
1.	Construction around scheduled league games	Will coordinate with RAP
2.	Potential increased construction cost due to inflation	Escalation and contingency are included in the cost estimate
3.	Potential delays for permit approvals	Will work with the design and environmental team to determine the best time to apply
4.	Potential long lead time for procurement	Will reference similar projects that will be built before this project and work with vendors for a more accurate timeframe

Questions

Noel Le

Watershed Management Group

Noel.Le@ladwp.com

Art Castro

Watershed Management Group

Art.Castro@ladwp.com

The Nature Conservancy & CA State Parks


Bowtie Demonstration Project

Kelsey Jessup

Urban Conservation Program Director

The Nature Conservancy

Project Location



Project Description

- The Bowtie Demonstration Project is a multi-benefit stormwater management and habitat enhancement project
- Partnership between TNC and CA State Parks
- Located on the CA State Parks' owned Bowtie Parcel in Northeast Los Angeles
- Project will be ~2.5 acres on the northern-most area of the site
- State Parks has completed conceptual designs for the full 18-acre site to become a publicly accessible open space
- The Bowtie Demonstration Project will be a catalyst for future phases at the Bowtie Parcel and will address the most severe water quality issues as identified through the water quality priority analysis done in advance of selecting the site

Project Description

Estimated Completion Date: December 2024

PROJECT GOALS



Improve water quality



Enhance habitat



Increase public access



Provide educational opportunities



Clean up historic contamination




STORMWATER CAPTURE & HABITAT
MANAGEMENT PROJECT
BOWTIE PARCEL

Project Benefits

- * Contributes to regional water self reliance by reusing stormwater onsite
- * Addresses risk from climate change by providing multiple community benefits, including reducing urban heat and mitigating flood risk
- * **Improves water quality by treating 100% dry weather flows**
- * **Enhances habitat and increases biodiversity**
- * Creates approximately 2 acres of publicly accessible open space and passive recreational opportunities through trails, boardwalks and educational elements and programming





Drainage area of 2,775 acres

Estimated annual treatment of 7.5 million gallons of dry weather flow

Approximately 18-acre feet of water treatment capacity

Statewide Priorities



- * Utilize natural infrastructure
- * Drought preparedness through water reuse onsite
- * Climate resilience
- * Strengthen partnerships with local, federal, and Tribal governments, water agencies and irrigation districts, and other stakeholders.

CEQA & Permit Status

CEQA/Permit Document (List all per EIF)	Start Date	End Date
CEQA	May 2022	January 2023
LADWP Right of Entry	June 2022	December 2022
Construction Stormwater Permit	TBD	
City of Los Angeles Building Permits		December 2022
LA County Flood Control Permit	June 2022	December 2022

Project Budget

Budget Category	Grant Request	Cost Share	Other Cost	Totals
A. Project Administration	\$275,000	\$75,000	\$0	\$350,000
B. Land Purchase/ Easement	\$0	\$0	\$0	\$0
C. Planning/Design Engineering/ Environmental Documentation	\$0	\$0	\$686,697	\$686,697
D. Construction/ Implementation	\$4,869,071	\$0	\$2,160,180	\$7,029,251
Totals	\$5,144,071	\$75,000	\$2,846,877	\$8,065,948
Minimum Grant Amount Needed:	\$4,869,071			

Project Schedule

Budget Categories	Start Date	End Date
A. Project Administration	July 2018	December 2024
B. Land Purchase/Easement	N/A	N/A
C. Planning/Design/Engineering/Environmental Documentation	February 2018	February 2023
D. Construction/Implementation	June 2023	December 2024

Expected Challenges/Delays

- * While CEQA and permitting is not yet complete, we have started the process and are confident we will stay on track to meet our project deadlines.
- * The Project is exempt from local cost share due to its location in a DAC. We have secured funding for all of design and a portion of implementation, but the funding is mostly through state sources and thus not eligible as match.
- * We are applying for SCWP funds. The Upper LA Region has limited funding available so we are aiming mostly for maintenance funds for the first five years after project completion.
- * TNC continues to seek additional funds from other sources, including private foundations and the CA Wildlife Conservation Board. This project is a priority for TNC and CA State Parks.
- * We expect to complete the project by December 2024.

Questions

- * Kelsey Jessup
- * Urban Conservation Project Director, The Nature Conservancy
- * kelsey.Jessup@tnc.org
- * 650-248-8878

